Project Specification

The contractor shall provide all labour, plant and materials required for the **structural steel** works, including *connections*, fixings and temporary bracing. Members shall be fabricated in accordance with the approved shop drawings and erected plumb, level and true to line within the tolerances given in the specification.

Ragged paragraph: the engineer may inspect any part of the works at any reasonable time and the contractor shall give access, assistance and the information the engineer requires.

Centred note: all dimensions are in millimetres unless noted otherwise.

Revision B — issued 12/10/2026

- Grade S355 steel for primary members.
- Hot-dip galvanised bolts, nuts and washers.
- Office efficient fluid workflow, café façade naïve.

Left column: welds shall be continuous unless shown otherwise and shall be inspected visually before painting. Defective welds shall be cut out and replaced.

Right column: surfaces shall be blast cleaned to Sa 2½ and primed within four hours of cleaning, before any visible rusting occurs.

Serif paragraph: Total contract sum $1,234,567.89 including 20% contingency.

```
Mono line: BEAM-01 356x171x51 UB L=6000
```